CD1.20

TREE SCHEDULE

No.	DIAM.	SPREAD Ø	HEIGHT
TE/1	0.65	16	16
TE/2	0.70	18	16
TE/3	1.30	20	20
TE/4	1.60	14	20
TE/5	1.10	20	16
TE/6	0.80	16	16
TE/7	0.40	4	6
TE/8	0.40	12	16
TE/9	0.65	15	17
TE/10	0.65	15	17
TE/11	0.65	15	17
TE/12	0.70	18	16
TE/13	0.70	18	16
TE/14	0.40	4	3
TE/15	0.40	4	3
TE/16	0.35	4	3
TE/17	0.50	6	6
TE/18	0.50	4	6
TE/19	0.35	10	6
TE/20	0.20	8	6
TE/21	0.20	8	6
TE/22	0.20	8	6
TE/23	0.50	12	8
TE/24	0.20	8	8
TE/25	0.20	8	8
TE/26	0.20	8	8
TE/27	0.20	4	6
TE/28	0.20	4	6
TE/29	0.15	4	6
TE/30	0.20	4	6
TE/31	0.20	4	6
TE/32	0.20	4	3
TE/33	0.30	8	10
TE/34	0.20	8	6
TE/35	0.20	8	6
TE/36	0.20	8	6
TE/37	0.20	8	6
TE/38	0.20	8	6
TE/39	0.20	8	6
TE/40	0.20	8	6
TE/41	0.15	4	6
TE/42	0.15	4	6
TE/43	0.15	4	6
TE/44	0.15	4	6
TE/45	0.20	6	8
TE/46	0.20	6	8
TE/47	0.20	4	6
TE/48	0.20	6	6
TE/49	0.20	6	6
TE/50	0.20	6	6
TE/51	0.65	14	12
TE/52	0.40	6	8
TE/53	0.40	6	8
TE/54	0.95	22	18
TE/55	0.80	10	10
TE/56	0.65	20	12
TE/57	0.20	4	6
TE/58	0.20	4	6
TE/59	0.20	4	6
TE/60	0.20	4	6
TE/61	0.20	4	6
TE/62	0.35	10	8
TE/63	0.20	6	6
TE/64	0.30	10	10
TE/65	0.70	14	14
TE/66	0.80	16	14
TE/67	1.00	18	18
TE/68	0.80	16	8
TE/69	0.60	8	8
TE/70	1.20	18	15
TE/71	0.90	18	15
TE/72	1.30	22	17
TE/73	0.90	22	17
TE/74	0.90	16	16
TE/75	0.90	16	16
TE/76	1.00	18	18
TE/77	1.00	18	18
TE/78	1.20	16	18
TE/79	1.00	14	12
TE/80	0.80	14	16
TE/81	0.60	12	10
TE/82	0.70	6	10
TE/83	0.15	4	10
TE/84	0.15	4	10
TE/85	0.15	4	10
TE/86	0.15	4	10
TE/87	0.50	18	14
TE/88	0.80	20	18
TE/89	0.80	20	18
TE/90	0.90	22	18
TE/91	1.00	22	18
TE/92	0.80	16	10
TE/93	0.40	8	8
TE/94	0.40	8	8
TE/95	0.40	8	8
TE/96	0.40	8	8
TE/97	0.65	8	8
TE/98	0.65	8	8
TE/99	0.70	12	10
TE/100	0.70	12	10
TE/101	0.40	8	10
TE/102	0.65	12	10
TE/103	0.40	10	10
TE/104	0.80	16	12
TE/105	0.80	16	12
TE/106	0.40	10	10
TE/107	0.40	10	10
TE/108	1.30	28	18
TE/109	1.20	14	14
TE/110	1.30	20	16
TE/111	0.30	8	8
TE/112	1.00	22	16

TREE DIAMETER MEASURED APPROXIMATELY 1.5M ABOVE GROUND LEVEL. TREE SPREADS ARE SYMBOLIC ONLY AND ARE REPRESENTATIVE OF THE GENERALISED CANOPY SIZE. TREE BOLE MAY NOT SIT CENTRALLY TO THE CANOPY. TREE HEIGHT ESTIMATED FROM GROUND LEVEL.

N

NOTES

THIS SURVEY IS ORIENTATED TO ORDNANCE SURVEY GRID NORTH. THE SURVEY IS TO A PLANE GRID. HORIZONTAL MEASUREMENTS TAKEN FROM THIS SURVEY WILL BE GROUND DISTANCES.

SITE CENTRE: E 437424, N 121309

LOCAL SCALE FACTOR: 0.9996185

ALL LEVELS RELATE TO ORDNANCE SURVEY DATUM GENERATED BY ACTIVE GPS NETWORK.

DRAINAGE:-

NO ALLOWANCE HAS BEEN MADE FOR SUB SURFACE ACCESS TO MANHOLES OR INVERTS AND PIPE BEDS, DEPTHS OR BELOW GROUND OBSTRUCTIONS AND ENTIRE FROM THE SURFACE AND THUS WILL ONLY BE APPROXIMATE. ANY FLOW TYPES (FOUL WATER, SURFACE WATER OR COMBINED) ARE ASSUMED AND THEREFORE REQUIRE VERIFICATION.

ROAD MARKINGS:-

ROAD MARKINGS DISPLAYED ARE SYMBOLIC. LENGTH, SPACING AND THICKNESS ETC. ARE INDICATIVE ONLY.

LEGEND

- 32.21 SPOT LEVEL
- SURVEY STATION
- SAPLING
- BUSHES/SHRUB
- TREE (INDICATIVE ONLY)
- HEDGE/AREA OF UNDERGROWTH
- 50.00 CONTOUR
- GATE
- OVERHEAD CABLE
- FENCE
- 1 PHOTOGRAPH LOCATION AND NUMBER

ABBREVIATIONS

AS	ARCH LEVEL	LB	LETTER BOX
AV	AIR VALVE	LP	LAMPOST
B	BOLLARD	MH	MANHOLE
BE	BELISHA BEACON	MKR	MARKER
BH	BOREHOLE	OHC	OVERHEAD CABLE
BL	BED LEVEL	OpL	OPENING LEVEL
BS	BUS STOP	OSBM	OS BENCHMARK
BT	BT PILLAR	PB	PILLAR
CB	CLOSED BOARD FENCE	PW	POST AND RAIL FENCE
CL	CHAIN LINK FENCE	PWi	POST AND WIRE FENCE
CATV	CABLE TELEVISION COVER	PEC	PEDESTRIAN CROSSING
CC	CONTROL CABIN	PM	PARKING METER
CH	CHAINAGE	PO	POST OFFICE
Conck	CONCRETE PANEL FENCE	RWL	RETAINING WALL
CPY	CANOPY	SAP	SAPLING
CrL	CROWN LEVEL	SEC	SECURITY CAMERA
Cay	CABLE STAY	SGY	STRIP GULLY
CTV	CABLE TELEVISION POINT	SL	SIGNAL LEVEL
CYR	CYCLE RACK	SP	SIGNPOST
DK	DROPPED KERB	SpL	SPRINGING LEVEL
DP	DOWNPIPE	SV	STOP VALVE
EIP	ELECTRIC INLET POINT	Tac	TACTILE PAVING
EC	ELECTRICITY INSPECTION COVER	TBS	TRAFFIC BOLLARD
EP	ELECTRICITY SUPPLY POLE	TE/1	TREE = NUMBER
ER	EARTH ROD	THL	THRESHOLD LEVEL
Fh	FIRE HYDRANT	TL	TRAFFIC LIGHT
GY	GULLY	TP	TOP OF FENCE
GDP	GUTTER AND DOWNPIPE	TpW	TOP OF WALL
GP	GATE POST	TP	TELEPHONE POLE
Gpi	GAS PIPE	WiM	WIRE MESH FENCE
GV	GAS VALVE	WoF	WOOD FENCE, FENCE
IC	INSPECTION CHAMBER	WLV	WATER LEVEL
IL	INVERT LEVEL	WM	WATER METER
IR	IRON RAILING FENCE	WO	WASH OUT
KO	KERB OUTLET		

STATION CO-ORDINATES

STATION	EASTING	NORTHING	LEVEL	DESCRIPTION
STN1	437287.33	121004.25	38.05	Survey Nail
STN4	437275.29	121004.24	37.78	Survey Nail
STN8	437252.01	121188.89	37.73	Survey Nail
STN9	437265.71	121609.09	34.27	Survey Nail
STN10	437274.65	121408.18	36.22	Survey Nail
STN11	437275.86	121327.79	37.07	Survey Nail
STN12	437275.86	121229.79	37.97	Survey Nail
STN13	437243.15	121044.46	37.68	Survey Nail
STN14	437219.25	120965.24	37.69	Survey Nail

PLOT LOCATIONS



Rev	Date	Revision notes	By
*	*	*	*

DO NOT SCALE

Status

INFORMATION

Project

Halterworth Lane, Romsey.

Title

TOPOGRAPHICAL SURVEY AS OF 08.06.21 SHEET 1 OF 2

GLADMAN
Gladman House, Alexandria Way
Congleton Business Park
Congleton, Cheshire
CW12 1LB
Tel: 01260 288800
Fax: 01260 288801
www.gladman.co.uk

Drawn By	Publish Date	Scale(s)	Sheet Size
JW/JH	15.06.21	1:500	A0

Project no.	Drawing no.	Revision
2016-136	Topo_01_2D	0

TREE SCHEDULE

No.	DIAM.	SPREAD Ø	HEIGHT
TE/1	0.65	16	16
TE/2	0.40	8	16
TE/3	1.30	20	20
TE/4	1.60	14	20
TE/5	1.10	22	16
TE/6	0.40	8	16
TE/7	0.40	8	16
TE/8	0.40	12	16
TE/9	0.65	10	17
TE/10	0.65	15	17
TE/11	0.65	15	17
TE/12	0.95	18	17
TE/13	0.70	18	16
TE/14	0.40	4	3
TE/15	0.15	4	6
TE/16	0.15	4	6
TE/17	0.20	8	6
TE/18	0.50	4	6
TE/19	0.35	10	6
TE/20	0.20	8	6
TE/21	0.20	8	6
TE/22	0.20	8	6
TE/23	0.50	12	8
TE/24	0.20	8	8
TE/25	0.20	8	8
TE/26	0.20	8	8
TE/27	0.20	4	6
TE/28	0.15	4	6
TE/29	0.15	4	6
TE/30	0.15	4	6
TE/31	0.20	6	6
TE/32	0.20	4	3
TE/33	0.20	8	6
TE/34	0.20	8	6
TE/35	0.20	8	6
TE/36	0.20	8	6
TE/37	0.20	8	6
TE/38	0.20	8	6
TE/39	0.20	8	6
TE/40	0.20	6	6
TE/41	0.15	4	6
TE/42	0.15	4	6
TE/43	0.15	4	6
TE/44	0.15	4	6
TE/45	0.20	6	8
TE/46	0.20	6	8
TE/47	0.20	4	6
TE/48	0.20	4	6
TE/49	0.20	6	6
TE/50	0.20	6	6
TE/51	0.45	14	12
TE/52	0.40	8	8
TE/53	0.20	4	6
TE/54	0.95	22	19
TE/55	0.80	10	10
TE/56	0.20	4	6
TE/57	0.20	7	6
TE/58	0.20	4	6
TE/59	0.20	4	6
TE/60	0.20	4	6
TE/61	0.20	4	6
TE/62	0.35	10	6
TE/63	0.25	8	6
TE/64	0.30	10	10
TE/65	0.70	14	14
TE/66	0.70	14	14
TE/67	1.00	18	18
TE/68	0.80	16	8
TE/69	0.60	8	8
TE/70	1.30	18	15
TE/71	1.00	14	15
TE/72	1.30	22	17
TE/73	0.90	22	17
TE/74	0.90	22	17
TE/75	0.90	16	16
TE/76	1.00	22	18
TE/77	1.00	18	18
TE/78	1.20	16	18
TE/79	0.80	14	16
TE/80	0.80	14	16
TE/81	0.80	20	16
TE/82	0.70	8	10
TE/83	0.15	4	10
TE/84	0.15	4	10
TE/85	0.15	4	10
TE/86	0.15	4	10
TE/87	0.50	16	14
TE/88	0.80	20	18
TE/89	0.90	22	18
TE/90	0.90	22	18
TE/91	1.00	22	18
TE/92	0.40	16	10
TE/93	0.40	8	8
TE/94	0.40	8	8
TE/95	0.40	8	8
TE/96	0.40	8	8
TE/97	0.40	8	8
TE/98	0.65	8	8
TE/99	0.30	5	5
TE/100	0.70	12	10
TE/101	0.40	8	10
TE/102	0.40	10	10
TE/103	0.40	10	10
TE/104	0.55	12	10
TE/105	0.80	16	12
TE/106	0.40	10	10
TE/107	0.40	8	10
TE/108	1.50	28	18
TE/109	1.20	14	14
TE/110	1.30	20	16
TE/111	0.30	5	8
TE/112	1.00	22	18

TREE DIAMETER MEASURED APPROXIMATELY 1.5M ABOVE GROUND LEVEL. TREE SPREADS ARE SYMBOLIC ONLY AND ARE REPRESENTATIVE OF THE GENERALISED CANOPY SIZE. TREE BOLE MAY NOT SIT CENTRALLY TO THE CANOPY. TREE HEIGHT ESTIMATED FROM GROUND LEVEL.

NOTES

THIS SURVEY IS ORIENTATED TO ORDNANCE SURVEY GRID NORTH. THE SURVEY IS TO A PLANE GRID. HORIZONTAL MEASUREMENTS TAKEN FROM THIS SURVEY WILL BE GROUND DISTANCES.

SITE CENTRE: E 437424, N 121309

LOCAL SCALE FACTOR: 0.9996185

ALL LEVELS RELATE TO ORDNANCE SURVEY DATUM GENERATED BY ACTIVE GPS NETWORK.

DRAINAGE:-

NO ALLOWANCE HAS BEEN MADE FOR SUB SURFACE ACCESS TO MANHOLES OR INSPECTION AND FIRE BODS, SHOTING OR BLOCKING OF SURFACE CROSSING MANHOLES FROM THE SURFACE AND THUS WILL ONLY BE APPROXIMATE. ANY FLOW TYPES (FOUL WATER, SURFACE WATER OR COMBINED) ARE ASSUMED AND THEREFORE REQUIRE VERIFICATION.

ROAD MARKINGS:-

ROAD MARKINGS DISPLAYED ARE SYMBOLIC. LENGTH, SPACING AND THICKNESS ETC. ARE INDICATIVE ONLY.

LEGEND

- SP.EL — SPOT LEVEL
- SURVEY STATION
- SAPLING
- BUSHES/SHRUB
- TREE (INDICATIVE ONLY)
- HEDGE/AREA OF UNDERGROWTH
- 99.00 — CONTOUR
- GATE
- OVERHEAD CABLE
- FENCE
- 1 — PHOTOGRAPH LOCATION AND NUMBER

ABBREVIATIONS

AG	ARCH LEVEL	LB	LETTER BOX
AV	AIR VALVE	LP	LAMPOST
B	BOLLARD	MH	MANHOLE
BE	BELISHA BEACON	MKR	MARKER
BH	BOREHOLE	NHC	OVERHEAD CABLE
BL	BED LEVEL	Opl.	OPENING LEVEL
BS	BUS STOP	OSBM	OS BENCHMARK
BT	BT PILLAR	PB	PILLAR
CB	CLOSED BOARD FENCE	P/R	POST AND RAIL FENCE
CL	CHAIN LINK FENCE	P/W	POST AND WIRE FENCE
CATV	CABLE TELEVISION COVER	PEC	PEDESTRIAN CROSSING
CC	CONTROL CABIN	PM	PARKING METER
CH	CHAINAGE	PO	PARKING PO
Conck	CONCRETE PANEL FENCE	RWL	RETAINING WALL
CPY	CANOPY	SAP	SAPLING
C/L	CROWN LEVEL	SEC	SECURITY CAMERA
Cably	CABLE STAY	SGY	STRIP GULLY
CTV	CABLE TV DIVISION POINT	SL	SIGNAL LEVEL
CYR	CYCLE RACK	SP	SIGNPOST
DK	DROPPED KERB	Spl.	SPRINGING LEVEL
DP	DOWNPIPE	SV	STOP VALVE
EIP	ELECTRIC INLET POINT	Tac	TACTILE PAVING
EC	ELECTRICITY DISTRIBUTION COVER	TBS	TRAFFIC BOLLARDS
EP	ELECTRICITY SUPPLY POLE	TE/1	TREE = NUMBER
ER	EARTH ROD	THL	THRESHOLD LEVEL
FH	FIRE HYDRANT	TL	TRAFFIC LIGHT
G	GULLY	TP	TOP OF FENCE
G/DP	GULLY AND DOWNPIPE	TyW	TOP OF WALL
GP	GATE POST	TP	TELEPHONE POLE
Gpl	GAS PIPE	WM	WIRE MESH FENCE
GV	GAS VALVE	W/F	WIRE FENCE, FENCE
IC	INSPECTION CHAMBER	WLY	WATER LEVEL
IL	INVERT LEVEL	WM	WATER METER
I/R	IRON RAILING FENCE	WO	WASH OUT
KO	KERB OUTLET		

STATION CO-ORDINATES

STATION	EASTING	NORTHING	LEVEL	DESCRIPTION
STN/1	437287.33	121004.25	38.05	Survey Nail
STN/4	437275.29	121004.24	37.78	Survey Nail
STN/8	437252.01	121188.89	37.73	Survey Nail
STN/9	437265.71	121609.09	34.27	Survey Nail
STN/10	437274.65	121408.18	36.22	Survey Nail
STN/11	437275.86	121208.79	37.07	Survey Nail
STN/12	437275.86	121129.79	37.97	Survey Nail
STN/13	437243.15	121044.46	37.68	Survey Nail
STN/14	437219.25	120965.24	37.69	Survey Nail

PLOT LOCATIONS



Rev	Date	Revision notes	By
*	*	*	*

DO NOT SCALE

Status

INFORMATION

Project

Halterworth Lane, Romsey.

Title

TOPOGRAPHICAL SURVEY AS OF 08.06.21 SHEET 2 OF 2

GLADMAN
Gladman House, Alexandria Way
Congleton Business Park
Congleton, Cheshire
CW12 1LB
Tel: 01260 288800
Fax: 01260 288801
www.gladman.co.uk

Drawn By	Publish Date	Scale(s)	Sheet Size
JW/JH	15.06.21	1:500	A0

Project no.	Drawing no.	Revision
2016-136	Topo_02_2D	0